STORM WATER POLLUTION PREVENTION PLAN for Chaney Enterprises – King George RMC Plant (VAG110128) 13250 James Madison Pkwy, King George, VA 22485

Prepared by: Victor Vilece, Assistant Project Manager/Land Chaney Enterprises, LP 2410 Evergreen Rd., Suite 201 Gambrills, MD 21054

January 2019

TABLE OF CONTENTS

1. Introduction

Emergency Telephone Numbers Management Approval Storm Water Pollution Prevention Plan Purpose Statement

2. Facility Overview

Description Location SIC/NAICS Site Drainage Industrial Activities and Potential Pollution Sources Facility Security Discharge Information Sampling Data

3. Best Management Practices

Operational Controls

Housekeeping Preventive Maintenance Spill Prevention and Cleanup Sediment and Erosion Control Employee Training

Pollution Prevention Committee

Source Controls

Treatment BMP's

Runoff BMP's

4. Monitoring Plan

Discharge Points and Flow Characteristics Sampling Data Summary Visual Monitoring Unintended Discharges

5. Inspections

Comprehensive Site Compliance Evaluation Routine Inspections and Record Keeping

6. Compliance With SARA Title III

7. Consistency With Other Statutes and Plans

8. Administration of SWPPP

Access to SWPPP Amendments to the SWPPP Signatures

List of Figures

Figure 1: Map of Facility Figure 2: Topographic Map Figure 3: Diagram of Facility

List of Tables

Table 1: Existing Storm Water Drainage and Discharge Points Table 2: Material Inventory Table 3: SWPPP Implementation Schedule Table 4: BMP Inspection Schedule

List of Appendices

Appendix A: Emergency Contact Information Chaney Appendix B: Enterprises Environmental Inspections Program (CEEIP) Form Appendix C: pH Log Appendix D: Air Emissions Log Appendix E: Environmental Education Seminar Sign-In Sheet Appendix F: Environmental Education Seminar Evaluation Form Appendix G: SWPPP Compliance Assessment Form

1. Introduction

Business Office Location:	13250 James Madison Parkway, King George, VA 22485
Primary Emergency Contact Name: Title: Office Number: Cell: Email:	Fernando Rodriguez Plants Manager (540) 775-5003 (240) 419-0616 <u>frodriguez@chaneyenterprises.com</u>
Secondary Contact Name: Title: Cell: Email:	Jeff Slagle General Manager (540) 710-0075 jslagle@chaneyenterprises.com
State Agency:	Virginia Dept. of Environmental Quality (804) 698-4000 Specific Contact: Rebecca Vice Title: Compliance Auditor Office Number: 1-800-332-6542 Cell/Direct: (703) 583-3922
Federal Agency:	National Response Center (800) 424-8802

Storm Water Pollution Prevention Plan (SWPPP) Purpose Statement:

This SWPPP has been prepared by Chaney Enterprises for the King George RMC Plant in King George, Virginia. The SWPPP has been prepared in accordance with the requirements of COMAR 26.17.02 as described in the "Virginia General Discharge Permit" No. VAG110128.

2. Facility Overview

Description:

The facility produces concrete and stores sand and gravel for use in the ready-mix concrete batching operations. There are two large storm water management catch basins located on site. As well as one diesel storage tank and one water storage tank. A scale is located near the front entrance. Several radio towers and storage structures are on-site. There is also a truck repair shop, batch office, and storage sea containers located towards the middle of the site.

Location:

The batch plant is located at 13250 James Madison Pkwy, King George, Virginia 22485.

SIC/NAICS Codes:

SIC – 3273 Ready-Mix Concrete Facilities NAICS – 327320 Ready-Mix Concrete Manufacturing

Site Drainage:

The site is composed of the above described buildings, tanks, and storage area. There are two main drainage zones on-site with the majority of the water draining west/southwest. All water eventually drains into one of two storm water basins in the southeastern and southwestern corners of the site (See **Figure 3**). There are two outfalls (**DP1** and **DP2**) on the southern edge of the site. Water from the washout pits is treated and then drains to the southwest storm water basin via a series of underground pipes. The storm water basins ultimately discharge into an unnamed tributary of the Gingoteague Creek.

Industrial Activities and Potential Pollution Sources:

Industrial activities at the site which potentially may impact water quality from the introduction of pollutants include:

- Concrete batch production and admixtures
- Leaking petroleum from delivery and storage
- Aggregate storage

Facility Security:

The facility is located in a rural/commercial area. The facility has adequate lighting. Entry is by driveway from James Madison Parkway on the eastern side if the site. There is a chain link fence surrounding the site and it is gated and locked during non-working hours.

Discharge Information:

There are two (2) discharge points that handle both storm water and process water (**Figure 3**).

Sampling Data:

This site is permitted and is therefore required to be sampled quarterly. The parameters sampled for are pH, Total Suspended Solids (TSS), and flow. These constituents are analyzed according to direction provided by VADEQ. Discharge monitoring reports will be submitted on a quarterly basis to:

Virginia Department of Environmental Quality Northern Regional Office 13901 Crown Court Woodbridge, VA 22193

3. Best Management Practices (BMP's)

Operational Controls:

This facility has been evaluated for all applicable Operational Source Controls BMP's as established by the Virginia Department of Environmental Quality in the Virginia Erosion and Sediment Control Handbook, Second and Third Edition.

Housekeeping

Employees of Chaney Enterprises, LP are responsible for maintaining the facility in a clean and orderly manner. Areas which could contribute to storm water pollution will be kept so as to minimize potential to contribute contaminants.

Good housekeeping includes:

- -Neat and orderly storage of chemicals
- Chemical storage containers labeled
- Containment of sediment on site.
- Prompt cleanup and removal of spillage, and
- Storage of garbage and trash in a tight dumpster.

Preventive Maintenance

This site is inspected on a routine, periodic basis. Maintenance issues which are identified are addressed in a timely manner.

Facility equipment and storm water drainage structures are inspected monthly and serviced as needed.

Spill Prevention and Cleanup

Potential exists for petroleum spills during vehicle transfer. Spills at this time could contribute to contamination of receiving waters, Virginia regulations require proper design, and maintenance of all tanks and storage areas. Monitoring and record keeping is required, as is on-site spill response capability.

Sediment and Erosion Control

The facility is partially paved and during storm events there is the possibility for sediment transport to the settling basins on-site. Materials that could potentially be eroded are checked daily. If issues are found they are addressed immediately.

Employee Training

Employees of Chaney Enterprises, LP will undergo yearly training. This training includes:

- Environmental awareness
- Site Knowledge
- State regulations and permit requirements
- Plant contents
- Pollution prevention overview
- Spill response procedures
- Housekeeping procedures
- Treatment system functions
- Importance of compliance

Pollution Prevention Committee

Victor Vilece, Environmental Project Manager is responsible for overseeing, implementing, and maintaining this plan. In addition he is responsible for assisting plant personnel in the full and continual adherence to the plan. This includes making management aware of resource needs. He also oversees all sampling of discharges on a quarterly basis and prepares and submits all DMR's. He heads the implementation of the Storm Water Pollution Prevention Plan.

Jeff Slagle, Concrete Operations Manager, is also part of the Committee. His responsibility is to make the Plant Manager aware of new potential sources of storm water contamination as well as overseeing adherence to policy.

Fernando Rodriguez is the Virginia Regional Manager and is responsible for ensuring that the treatment systems are monitored daily and implementing BMP's on a daily basis.

All employees at this location are encouraged to bring to the attention of the committee members any deficiency they encounter, or any ideas for storm water protection they may have.

Source Controls:

This facility has been evaluated for all applicable Source Control BMP's as established by the Virginia Department of Environmental Quality in the Virginia Erosion and Sediment Control Handbook, Second and Third Edition.

Treatment BMP's

Two pH control systems are located at the King George Facility. One is located in the truck washout basins and one is located at the southeastern storm water basin (**Figure 3**). They function as automated pH neutralizing systems for washout/wastewater and storm water runoff. They utilizes non-hazardous Sodium Bisulfate with proper storage on-site. This system is checked on a daily

basis (during plant operations hours) and on-site personnel ensure that they are functioning properly. Any issues with the system will be reported to the pollution prevention committee members for immediate correction.

Run-Off BMP's

Storm water run-off from the property discharges into a tributary of the Gingoteague Creek from two (2) discharge points. There is no evidence of any erosional or depositional problems associated with this drainage – therefore addition flow controls have not been necessary. This situation is routinely checked however. Stockpiled material consists of varying sizes of aggregate, sand, and recycled concrete material. This material is stored to minimize the surface area exposed to storm water. Any material seen migrating from the piles is picked up by a front-end loader and placed back into the stock pile.

Enhanced and / or Additional BMP's

In case enhanced or additional BMP's are deemed necessary, a schedule for implementation will be developed and incorporated into this plan within 30 days of determination. The new BMP's will be implemented with all due diligence. Unless otherwise directed by VADEQ, all newly required operational BMP's will be implemented within 15 days of direction. BMP's that require capital expenditures will be implemented within six months.

4. Monitoring Plan

Discharge Points and Flow Characteristics:

There are two (2) surface water discharge points from the facility into a tributary of Gingoteague Creek. The sampling and analytical methods used shall conform to procedures for the analysis of pollutants as identified in 40 CFR Part 136 – "Guidelines Establishing Test procedures for the Analysis of Pollutants" unless otherwise directed by VADEQ.

Sampling Data Summary:

Sampling is done quarterly as described in the "Virginia General Discharge Permit" No. VAG110128.

Visual Monitoring:

The surface water discharge points are visually inspected quarterly. This is done in conjunction with review of any maintenance issues regarding the diversion structures. A comprehensive inspection is done every year by onsite personnel or a member of the Pollution Prevention Committee.

Unintended Discharges:

There have been no reported incidents of significant leakage at this location.

5. Inspections

Comprehensive Site Compliance Evaluation:

Inspections are performed daily and quarterly, and documented with a checklist (see **Appendix B, C, and D**). The inspection reports are retained for three (3) years onsite as well as in the corporate office. Signature on the form signifies certification that the site is in compliance with the SWPPP and the "Virginia General Discharge Permit" No. VAG110128.

Routine Inspections and Record Keeping:

Inspections as required by the Virginia Department of Environmental Quality as described in the "Virginia General Discharge Permit" No. VAG110128 will be conducted by the Plant's Manager or his authorized representative. Walkthrough inspections are conducted quarterly, and a comprehensive inspection is done annually. Reports of visual monitoring done by facility staff will be submitted to the Environmental Project Manager. Deficiencies identified will be scheduled for correction. When necessary, a schedule of compliance will be developed and submitted into this Plan. Records of all monitoring information, inspection reports, and any other compliance documentation will be kept for three (3) years onsite as well as at the corporate the office. All information described above is available for review by contacting the Environmental Project Manager.

6. Compliance with SARA Title III

Chemicals subject to SARA Title III. Section 3 includes diesel fuel. Diesel fuel is subject to the SPCC Plan requirements of the Clean Water Act. The SPCC Plan addresses compatibility, secondary containment, spill prevention, spill control, and drainage. The facility does not have a P.E. certified SPCC Plan. There have been no discharges of any material covered under SARA Title III at this facility for the past three (3) years.

7. Consistency With Other Statutes and Plans

Chaney Enterprises, LP is subject to certain requirements and schedules that pertain specifically to its reclamation areas. They do not impact the requirements under the Virginia Discharge Permit" No. VAG110128.

8. Administration of SWPPP

Access to SWPPP:

This plan will be retained on-site in the batch plant office and at the corporate office located at 2410 Evergreen Road, Gambrills, MD 21054. Upon request it shall be made

available to VADEQ. Any requests for a current copy or updates will be honored within two weeks of formal receipt of the request.

Amendments to the SWPPP:

The Plan shall be amended whenever there is a change in design, construction, operation, or maintenance of any BMP's that causes the Plan to be less effective in preventing storm water pollution. It will also be amended upon direction by VADEQ or when visual monitoring indicated a need for an amendment.

Storm Water Pollution Prevention Plan Changes:

Date	Individual Responsible for	Nature of Change
	Change	
July 2014	Dylan Drudul	Addition of 2 nd outfall
Nov 2016	Victor Vilece	Comprehensive Update
Jan 2019	Victor Vilece	Comprehensive Update

Signatures:

All reports required by the Virginia Department of Environmental Quality as described in the "Virginia General Discharge Permit" No. VAG110128, the applicable regulations and this Plan, and other documentation requested by the Virginia Department of Environmental Quality shall be signed by the Environmental Project Manager or an employee or agent with the authority as given by a principal executive officer. The Environmental Project Manager has been given overall responsibility for these matters by a principal executive officer. All persons signing documents a described above must make the following certification:

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person, or persons, who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

Sign:	Date:	3/1/19

Title: <u>Environmental Project Manager</u>

FIGURE 1: MAP OF FACILITY



FIGURE 2: TOPOGRAPHIC MAP





FIGURE 3: DIAGRAM OF FACILITY



Storm Water Pollution Prevention Plan King George Ready Mix Concrete Facility January 2019

TABLE 1 EXISITING STORM WATER DRAINAGE AND DISCHARGE POINTS

DRAINAGE ZONE/ DISCHARGE POINTS	STORM WATER DRAINAGE DESCRIPTION	POTENTIAL POLLUTION	POTENTIAL PROBLEMS
Facility Drainage	Natural Topography, site grading, and a system of underground pipes direct drainage throughout the site. A four (4) tier sediment basin will collect and treat all truck wash. Two (2) large storm water basins will collect and treat all storm water on- site.	Gasoline, Diesel Fuel, Hydraulic Oil/Fluids, Sediment	Diesel fuel/fluids may leak from trucks and equipment. Improper loading may result in sediment discharge. Run off from bulk materials and aggregate storage areas may result in excess sediment buildup. Improper loading at plant my result in sediment discharge.
DZ-1	Graded to direct water to the storm water basin in the southwest corner of the site and DP-1. Agg bins, fueling station, settling basins, pH treatment system, truck wash area, batch plant, office, shop, and scale are all located within this drainage zone.	Gasoline, Diesel Fuel, Hydraulic Oil/Fluids, Sediment	Diesel fuel/fluids may leak from trucks and equipment. Improper loading may result in sediment discharge. Aggregates may be carried by storm water.
DZ-2	Graded to direct water to the storm water basin in the southeast corner of the site and DP-2. Agg piles, recycled concrete, truck parking, and the site entrance are within this drainage zone.	Diesel Fuel, Hydraulic Oil/Fluids, Sediments	Diesel fuel/fluids may leak from trucks and equipment. Runoff from bulk material areas may result in excess sediment buildup.
DP-1	Located in the southwest corner of the site. The storm water basin collects treated wash water from the settlement basins/truck wash area. The basin allows for final settling before any discharge takes place.	Diesel Fuel, Hydraulic Oil/Fluids, Sediments	Diesel fuel may leak from fueling activity. Diesel fuel/fluids may leak from trucks and equipment. Runoff from aggregate storage areas and drum washing activities may result in excess sediment buildup.
DP-2	Located in the southeast corner of the site. The storm water basin collects flow from the entrance, truck parking area, and recycle pile.	Diesel Fuel, Hydraulic Oil/Fluids, Sediments	Diesel fuel/fluids may leak from trucks and equipment. Runoff from bulk material areas may result in excess sediment buildup.

Table 2 <u>MATERIAL INVENTORY</u>

TRADE NAME MATERIAL	PHYSICAL DESCRIPTION	STORM WATER POLLUTANTS
Sand, Gravel	Solid particles	Silicon, suspended solids, turbidity, sediment
Hydraulic oil/fluids	Brown oily petroleum hydrocarbon	Mineral oil
Gasoline	Colorless, pale brown or pink petroleum hydrocarbon	Benzene, ethyl benzene, toluene, xylene, MTBE
Diesel Fuel	Clear, blue-green to yellow liquid	Petroleum distillate, oil & grease, naphthalene, xylenes
Antifreeze/coolant	Clear green/yellow liquid	Ethylene glycol, propylene glycol, heavy metals (copper, lead, zinc)

TABLE 3SWPPP IMPLEMENTATION SCHEDULE


SWPPP FEATURE	TARGET IMPLEMENTATION DATE
Environmental compliance inspections (CEEIP) Appendix A	Quarterly
Implementation of SWM Control Measures	Daily
Inspection of Water Treatment System Appendix C	Daily
Visual Inspection of Batch Plant Air Filtration System Appendix D	Daily
Employee Environmental Education Appendix E	Annually: 4 th quarter
Environmental Education Program Evaluation Appendix F	Annually: 4 th quarter
SWPPP Compliance Assessment Appendix G	Annually: 4 th quarter

TABLE 4BMP INSPECTION SCHEDULE

SWPPP FEATURE	TARGET IMPLEMENTATION DATE
Drum Wash Basins	Inspect daily for sediment accumulation, Clean weekly or as needed.
Treatment Basin	Visually inspect daily for sediment accumulation and record freeboard measurement. Pump out sediments bi-annually or as needed.
pH Treatment Systems	Inspect pumps daily for sediment accumulation/blockage. Clean as needed.
Fuel Station	Visually inspect q uarterly for signs of wear and leaks.
Waste Concrete Storage	Visually inspect quarterly for proper containment. Clean residual waste as needed.
Material Storage Areas, Including Aggregate Stock Piles	Visually inspect quarterly for proper containment, labeling, and signs of leaks or spills.
Entrance, Yard, Berms, Curbs	Visually inspect quarterly for sediment accumulation, dust, and effectiveness in directing storm water.

For BMP Inspection logs see Appendix C, Appendix D, and Appendix E.

APPENDIX A EMERGENCY CONTACT INFORMATION





Appendix B I. General Information

CEEIP Inspection Form

deneral into	mation				CEEN INSPECTION FOR
Facility:			Permit #:		
Date:	Time:	Weather:		Phone:	
Facility			Site		
Address:			Manager:		
Inspector:					

II. Site Conditions		S۱	NPPP Or	Site: Yes	s 🗌 No 🗌 👘 DMR's On Site: Yes 🗌 No 🛄
		Conditio	on Range		Comments/Corrections Needed
	Great	Good	Fair	Poor	
E & S Control					
On-Site Storage					
Equipment/ Vehicles					
Roadways					
Air Pollution					
Discharge	Dischar	ging: Y	/ N		
Monitoring	pH:				
		the Court			

Additional Comments on Site Conditions:

III. pH Treatment System

	Questions	Site Corrections:	
Washout/Settling	Have washout basins/ponds been cleaned recently?		
Ponds	What is the pH in the settling area w/handheld probe?		
	What is the pH reading upon arrival?		
pH Controller	What is the Hi limit reading?		
	What is the Lo limit reading?		
	How much CO2/Sodium bisulfate is in the tank?		
Mixing	Does additional chemical need to be added/ tank filled?		
	Were site personal informed?		
	Is probe covered in residue and dirty?		Due Date:
pH Probe	Was probe cleaned with cleaning solution?	Days 1wk 2wk 3wk	
	What are readings before/after calibration with solution 7.0?		
	What are readings before/after calibration with solution 10.0?		
Piping	Is intake piping functional?		
	Is discharge piping functional?		Sign:
Comments on pH S	ystem Conditions:	<u> </u>	
Inspector			
Name	Signature		Date:

ame:	Signature:	Date:
-	2410 Evergreen Road Suite 201 Gambrills, Ma	ryland 21054
	WEB ChaneyEnterprises.com PHONE 888-42	4-2639

Storm Water Pollution Prevention Plan King George Ready Mix Concrete Facility

APPENDIX C <u>pH LOG</u>

Date	Time	Weather	pH Reading	Freeboard	Signature

APPENDIX D AIR EMISSIONS LOG

Date	Observer	Time	Differential Pressure Reading	Visible Emissions Yes/No	If Visible Emissions: Date/Time of Corrective Actions

APPENDIX E ENVIRONTMENTAL EDUCATION SEMINAR SIGN-IN SHEET

Date	Employee Name	Employee Signature

APPENDIX F ENVIRONTMENTAL EDUCATION SEMINAR EVALUATION FORM

Program Feature	Applicable? (Y/N)	Comments
Has a date been established for the annual seminar?		
Will all state and federal regulations be addressed?		
Will employees be informed of any changes to the SWPPP?		
Will there be any outside sources involved in the training program?		
Did the facility staff appear more informed after last year's program?		
Have there been any employee comments/suggestions?		
Name:		Date:
Signature:		
Title:	_	

APPENDIX G SWPPP COMPLIANCE ASSESSMENT

SWPPP Feature	Y/N	Comments
Have quarterly inspections been		
conducted and have form been		
completed and filed?		
Have BMP's been implemented		
and has the implementation		
schedule been adhered to?		
Has employee training been		
implemented?		
Has the Environmental Education		
Program been evaluated and		
forms filed?		
Have all changes to site function		
been addressed in the SWPPP?		
Name:		Date:
Cignoture		
Signature:		
Title:		